

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2019-20 Dated: 25-4-2019

APPROVED TENDER SCHEDULE - 'B'

Item-16

Name of Work:-Construction of Culverts in Maruthinagar layout and surabhi layout in kempegowda wardno-01

SI	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19	Cum	201.96	291.58	Rupees Two Hundred Ninety One and Paise Fifty Eight Only
2	KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed , concrete laid in layers not exceeding 15 cms, thick, well compacted , in foundation , including cost of all materials, Labour , HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19		25.25	4975.47	Rupees Four Thousand Nine Hundred Seventy Five and Paise Forty Seven Only
3	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 lte mo 37.59.2 SR 2018-19 (wall and bottom thickness 15cm.	Cum	63.75	6504.58	Rupees Six Thousand Five Hundred Four and Paise Fifty Eight Only
4	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	3.83	69206.04	Rupees Sixty Nine Thousand Two Hundred Six and Paise Four Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri SAMBASHIVA REDDY C	
				Rate	Rate In Words
5	Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading, unloading, etc., complete as per the direction of engineer in charge-	Sqm	122.40	4984.59	Rupees Four Thousand Nine Hundred Eighty Four and Paise Fifty Nine Only
6	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	201.96	82.60	Rupees Eighty Two and Paise Sixty Only
7	KSRB-4-1.1 : Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.1/ PWD SR 2018-19	Cum	28.56	5151.98	Rupees Five Thousand One Hundred Fifty One and Paise Ninety Eight Only

C. Sambashiva Reddy
Signature of the Contractor

[Signature]
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.